

KUBATURY ZEMNÝCH PRÁC

Trasa - P2

Staničení ZÚ: 0+00.000

Staničení KÚ: 0+579.728

<u>Staničení</u>	<u>Plocha výkopu (m2)</u>	<u>Objem výkopu (m3)</u>	<u>Znovu použitelný objem (m3)</u>	<u>Plocha násypu (m2)</u>	<u>Objem násypu (m3)</u>	<u>Součet objemů výkopu (m3)</u>	<u>Kum, znovu použitelný obj. (m3)</u>	<u>Součet objemů násypu (m3)</u>	<u>Hmotnice (m3)</u>
0+000.00	0.00	0.00	0.00	1.22	0.00	0.00	0.00	0.00	0.00
0+050.00	0.00	0.00	0.00	1.09	57.73	0.00	0.00	57.73	-57.73
0+100.00	0.22	5.42	5.42	0.09	29.45	5.42	5.42	87.18	-81.76
0+150.00	1.69	47.75	47.75	0.00	2.19	53.17	53.17	89.37	-36.20
0+200.00	1.69	84.45	84.45	0.00	0.00	137.62	137.62	89.37	48.25
0+250.00	1.22	72.53	72.53	0.00	0.05	210.15	210.15	89.42	120.73
0+300.00	0.15	34.10	34.10	0.14	3.50	244.25	244.25	92.92	151.33
0+350.00	0.10	6.13	6.13	0.11	6.14	250.38	250.38	99.07	151.31
0+400.00	0.24	8.32	8.32	0.08	4.75	258.70	258.70	103.82	154.88
0+450.00	1.24	36.79	36.79	0.00	2.07	295.49	295.49	105.88	189.61
0+500.00	2.26	87.38	87.38	0.00	0.00	382.88	382.88	105.89	276.99
0+550.00	1.41	91.62	91.62	0.00	0.00	474.49	474.49	105.89	368.61
0+579.72	0.00	20.90	20.90	0.00	0.00	495.39	495.39	105.89	389.51